

BRUCE ROAD WILDCAT CREEK PROJECT

SCOPE OF WORK

Wildcat Creek Project includes removal and disposal of the old single lane wooden bridge and appurtenances. Construction and removal of a detour bypass to be operational during the bridge removal and culvert installation. Hauling and compaction of fill material to reduce the road side slopes. Installation of two (2) corrugated steel culverts, bedding material, and rip-rap. Completion of the project includes reclamation, seeding, and erecting new fence in the disturbed area of the Project.